

Eddie Baza Calvo
Governor



Anthony C. Blaz
Director, Dept. of Admin.

GENERAL SERVICES AGENCY
Government of Guam
148 Route 1 Marine Drive Corp
Piti, Guam 96915

Ray Tenorio
Lt. Governor

Alfred F. Duenas
Deputy Director

August 07, 2015

Invitation for Bid GSA-094-15
RENOVATION OF THE PASEO BASEBALL STADIUM

AMENDMENT #2

1. Amend to change on page 29 of 32, under "SPECIFICATIONS" Item# 4 to the following:

FROM:

4. Remove and replace scoreboard with new Daktronics BA-2125 (or equal) single-sided baseball scoreboard displays HOME and GUEST team scores for up to 10 innings, total RUNS and HITS to 99 and ERR (errors) to nine for each team, team, AT BAT to 99, BALL to three, STRIKE to two, OUT to two, and H/E (hit or error) with field position number for the error. Scoreboard can show TIME or PITCH COUNT instead of AT BAT, as well as AT BAT or PITCH COUNT in place of H/E, hardwired, complete and ready to use. (1-EA.)

TO NOW READ:

4. Remove and replace scoreboard with new Daktronics BA-2125 (or equal) single-sided baseball scoreboard displays HOME and GUEST team scores for up to 10 innings, total RUNS and HITS to 99 and ERR (errors) to nine for each team, team, AT BAT to 99, BALL to three, STRIKE to two, OUT to two, and H/E (hit or error) with field position number for the error. Scoreboard can show TIME or PITCH COUNT instead of AT BAT, as well as AT BAT or PITCH COUNT in place of H/E, hardwired, complete and ready to use. (1-EA.) **Scoreboard must be installed after July 1, 2016**
2. Amend to replace page 32 of 32 with the attached "Revised 8/07/15 page 32 of 32" Attached.

All others remains unchanged.


CLAUDIA S. ACFALLE
Chief Procurement Officer

SPECIFICATIONS:

BIDDING ON/REMARKS:

- 17. Renovate Ticket Booth; repaint and replace all electrical fixtures as required; complete and ready to use. (LS – 1) _____
- 18. Assess, refurbish and/or replace all metal pipe railing as required with Size 5 Galvanized Schedule 40, 1-1/2"; apply two (2) coat ANSI approved paint to match existing (1,976 L.F. – Estimated) (LS – 1) _____
- 19. Remove and replace all chain link fencing attached to railing; fencing gauge (9 gauge 2" mesh galvanized) and make shall match or exceed existing fencing (1,976 L.F. – Estimated) (LS – 1) _____
- 20. Install new metal awning roof over fixed seating, complete with metal columns, beams, and gutters (115'-0" x 35'-0") adjacent to grandstand seating area with Butler style 24-gauge galvanized steel or equivalent. (LS – 2) _____
- 21. Prep and repaint stadium entrance (Includes concrete perimeter fence wall); color and trim as approved by owner. (LS – 1) _____
- 22. Furnish and install new upgrade Main Control Center (MCC) for lighting control (overhead field lighting distribution) for exterior Stadium lighting to meet new Load requirements, complete and ready to use. (LS-1) _____
- 23. Demolish existing outfield concrete wall and provide finish opening (20 ft. wide) For installation of new rolling service gate. (LS-1) _____
- 24. Furnish and install new Wall Mount Track 10 ft. high by 20 ft. long (net opening) Rolling Gate Chain Link Fence, complete with roll gate, tracks, privacy slats (green) And all hardware; wire shall be 2-1/4" x 11-1/2" gage commercial grade Galvanized mesh. (1-EA) _____
- 25. Level and fill with top soil all uneven areas of entire playing field (infield and outfield); Seed with like cover/grass; and irrigate until fully rooted to a minimum height of 1 Inch. Seeding of playing field shall exclude infield base running lane and outfield Warning track. Field work shall commence on July 1, 2016 _____

Warranty:

Successful Bidder to provide one (1) year warranty on all work to include labor, materials, and supplies. _____

NOTE:

Bidder is responsible to obtain any and all licenses/clearances as required by the Contractor's License Board to perform this contract. **Building Permit (if required)**

These specification were develop by the staff of the Department of Parks and Recreation and Approved by: RAYMOND F.Y. BLAS, Director DPR